

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21508-00-01  
Spot: SWNESW Sec/Twnshp/Rge: 2-26S-13W  
990 feet from S Section Line, 1650 feet from W Section Line  
Lease/Unit Name: LONG OWWO Well Number: A-1  
County: PRATT Total Vertical Depth: 4410 feet

Operator License No.: 32154  
Op Name: SAGEBRUSH OPERATING L.L.C.  
Address: 1700 LINCOLN, SUITE 2200  
DENVER, CO 80203

Conductor Pipe: Size feet: 8 1/2 3.33  
Surface Casing: Size 8.625 feet: 438  
Production: Size 4.5 feet: 4281 WITH 300 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/24/2002 3:30 PM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND BACK TO 3800'. 1ST PLUG AT 800' WITH 50 SX CMT & 10 SX GEL . 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/24/2002 5:00 PM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 3924'. ANHYDRITE @ 770'. SAND BACK TO 3800' & 1 SX CMT ON TOP. CASING PATCH AT 2580' HUNG UP BAILER. LOADED HOLE. HOLE LOADED OKAY. 1ST PLUG SPOT 15 SX GEL & 50 SX CMT AT 811'. 2ND PLUG AT 456' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. GOOD CIRCULATION.

RECEIVED

JUL 30 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2060' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

INVOICED JUL 26 2002

DATE 7-30-02

NO. 2003060123

Form CR-2/3

