

11-29

To: 1 040366
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,508 - 00.00
SW NE SW, SEC. 2, T 26 S, R 13 W/E
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004
Operator: Vincent Oil Corporation
Name & Address: 125 North Market, Suite 1110
Wichita, KS 67202

Lease Name Long "A" Well # 1
County Pratt 13/6.18
Well Total Depth 4190 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 438


Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2 p.m. Day: 29 Month: 11 Year: 19 89

Plugging proposal received from Bruce Wagner
(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 4239' Perfs at 4144-51, 4122-26' Elevation 1911' GL
1st plug sand back to 4070' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.



Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2:45 p.m. Day: 29 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT Junk in hole=approximately 3476' of 3 1/2" fiberglass tubing
1st plug sanded back to 4070' and dumped 4 sx cement on top of sand bridge with bailer,
2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 500 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2485' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE DEC 08 1989

WTA NO. 26723

11-29

Signed Stephen J. Pfeifer (TECHNICIAN)