

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20721-00-00
Spot: NENE Sec/Twnshp/Rge: 27-30S-18W
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: UNRUH D Well #: 2-27
County: KIOWA Total Vertical Depth: 5114 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5005		WITH 2 SX CMT
PROD	4.5	5113	1793	WITH 250 SX CMT
SURF	8.625	433		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/21/2014 2:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 5000' WITH 2 SX CMT. PLUG AT 1150' WITH 10 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 08/21/2014 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5005' WITH 2 SX CMT. 1ST PLUG AT 1158' WITH 10 SX GEL & 50 SX CMT.
2ND PLUG AT 482' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5060	5108		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION

RECEIVED

AUG 26 2014

KCC DODGE CITY

SEP 02 2014

CONSERVATION DIVISION
WICHITA, KS

9-9-14 ckm

Form CP-2/3