

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-20703-00-00  
Spot: NESENE Sec/Twnshp/Rge: 31-34S-2E  
1740 feet from N Section Line, 330 feet from E Section Line  
Lease Name: HASLOUR Well #: 2A  
County: SUMNER Total Vertical Depth: 3561 feet

Operator License No.: 32887  
Op Name: ENDEAVOR ENERGY RESOURCES, LP  
Address: 110 N MARIENFELD, STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3444		
PROD	4.5	3506		160 SX
SURF	8.625	258		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2014 5:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: GUS MYERS Company: ENDEAVOR ENERGY RESOURCES Phone: (918) 244-8063

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/29/2014 7:30 PM KCC Agent: DAN FOX

Actual Plugging Report:

ON 7/29/2014 OPERATOR RAN IN WELL WITH WIRE LINE TO TAG BOTTOM AND PERFORATE CASING @ 308'. WIRE LINE HIT SMETHING SOLID AT 2285', OPERATOR STATES THEERE COULD BE PARTED TUBING AT 2285' AND THERE IS A POSSIBLE CASING LEAK AT 2124' TO 2126'. OPERATOR RAN IN 2 3/8" TUBING TO 2280' AND PUMPED 23 SXS OF COMMON CEMENT WITH 3% CC AND LET IT SET UP FOR OVER AN HOUR, RAN N AND TAGGED TOP OF CEMENT AT 2240' SO OPERATOR RAN BACK IN AT 2235' AND PUMPED ANOTHER 50 SXS OF SAME SLURRY, WAITED UNTIL MID AFTERNOON TO TAG AGAIN AND THIS TIME THE 2ND TAG WAS AT 1500'. OPERATOR THEN PULLED UP TO 2080' AND PUMPED ANOTHER 15SXS, WAITED ANOTHER 1 1/2 THEN TAGGED TOP OF CEMENT AT 1582'. PULLED TUBIG UP TO 308' AND CIRCULATED 110 SXS OF CEMENT TO SURFACE. CAME BACK AFTER TWO DAYS TO CHECK TOP PLUG AND CEMENT HAD NOT DROPPED. JOB COMPLETE.

Perfs:

Top	Bot	Thru	Comments
3166	3176	TBG	

Remarks: CONSOLIDATED CEMENT TICKET #5220000909

Plugged through: TBG

District: 02

Signed Daniel Fox  
9.9.14 ckm (TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION  
**SEP 09 2014**  
CONSERVATION DIVISION  
WICHITA, KS