

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-01175-00-01
Spot: SWNWSW Sec/Twnshp/Rge: 35-19S-12W
1650 feet from S Section Line, 660 feet from W Section Line
Lease Name: PANNING Well #: 1
County: BARTON Total Vertical Depth: 3351 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3351		1172 SX
SURF	8.625	135		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2014 8:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: KENT STRUBE Company: HARTMAN OIL Phone: (620) 786-4161

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/1000 # hulls.
Holes in casing from 1561' - 3300'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/28/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3062' and pumped 150 sx cement w/400 # hulls. Pulled tubing to 1700' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 900'. Circulated cement to surface on casing with 65 sx cement. Pulled tubing and topped off casing w/10 sx cement. Tied to surface casing, pressured up and would not take cement. Cement had been circulated to surface in the past.

GPS: 38.35219 -09862620

Perfs:

Top	Bot	Thru	Comments
3332	3342		
3322	3324		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

SEP 08 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Bruce Rodie
(TECHNICIAN)

9.9.14 cpm

cm

SEP 02 2014