

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25965-00-00
Spot: NESWNWSE Sec/Twnshp/Rge: 24-20S-14W
1928 feet from S Section Line, 2123 feet from E Section Line
Lease Name: ELLINWOOD LAND & CATTLE Well #: 1-24
County: BARTON Total Vertical Depth: 3566 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	813		400 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/26/2014 12:00 AM
Plug Co. License No.: 33323 Plug Co. Name: PETROMARK DRILLING, LLC
Proposal Rcvd. from: ROBIN Company: PETROMARK DRILLING, LLC Phone: (316) 734-8977

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY WitnessType: NONE
Date/Time Plugging Completed: 08/26/2014 1:45 AM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @3500 w/50 sx
2nd plug @870 w/80 sx
3rd plug @220 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: BASIC

Plugged through: DP

Received
KANSAS CORPORATION COMMISSION

SEP 08 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Chris Neeley
9.9.14 ckm

(TECHNICIAN)

CM

SEP 02 2014