

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20731-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 18-30S-8W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MESSENGER 'T' Well #: 1-18
County: KINGMAN Total Vertical Depth: 4253 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4252	1800	75 SX
PROD	4.5	4253		
SURF	8.625	296		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/22/2014 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (316) 636-2737

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/22/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 4140' - CAPPED WITH 5 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 1800' PULLED CASING TO 1475' SPOTTED 35 SXS CEMENT. PULLED CASING TO 1000' SPOTTED 35 SXS CEMENT. PULLED CASING TO 350' CIRCULATED TO SURFACE WITH 125 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4204	4215		

Received
KANSAS CORPORATION COMMISSION
SEP 05 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS PLUGGING ALSO. PAST 10 YEAR TA.

Plugged through:

District: 02

Signed [Signature] (TECHNICIAN)

9.9.14 CKM

[Handwritten mark]