

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21130-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 29-23S-10W  
4569 feet from S Section Line, 440 feet from E Section Line  
Lease Name: BENJES Well #: 2  
County: RENO Total Vertical Depth: 3841 feet

Operator License No.: 31714  
Op Name: NOVY OIL & GAS, INC.  
Address: PO BOX 559  
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3841		175 SX
SURF	8.625	225		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/02/2014 12:00 AM  
Plug Co. License No.: 31714 Plug Co. Name: NOVY OIL & GAS, INC.  
Proposal Rcvd. from: KIRK GLENN Company: NOVY OIL & GAS Phone: (620) 282-2212

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/13/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3458' CAPPED WITH 5 SXS CEMENT ON TOP. PERFROATED CASING AT 1450', -880', & -255' WITH 4 SHOTS PER FOOT. RAN TUBING INTO 1445' SPOTTED 35 SXS CEMENT, WAITED TWO HOURS TAGGED TOC @ 1300'. RAN TUBING INTO 880' SPOTTED 35 SXS CEMENT WAITED TWO HOURS, TAGGED TOC @ 600'. RAN TUBING INTO 255' CIRCULATED TO SURFACE WITH 300 SXS OF CEMENT. CEMENT FELL BACK 65' INSIDE PIPE, AND 10' BETWEEN SURFACE CASING, CAPPED WITH 11 SXS CEMENT, ON 8/21/14.

Perfs:

Top	Bot	Thru	Comments
3655	3669		

Received  
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING OUT OF GREAT BEND, TICKET #63706

SEP 05 2014

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed \_\_\_\_\_

9.9.14 CKM

(TECHNICIAN)

✓