

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21277-00-00  
Spot: SENWNWNE Sec/Twnshp/Rge: 29-23S-10W  
4920 feet from S Section Line, 2180 feet from E Section Line  
Lease Name: BENJES Well #: 3  
County: RENO Total Vertical Depth: 3850 feet

Operator License No.: 31714  
Op Name: NOVY OIL & GAS, INC.  
Address: PO BOX 559  
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1703		
PROD	5.5	3836		110 SX
SURF	8.625	225		200 SX
SURF		238		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2014 12:00 AM  
Plug Co. License No.: 31714 Plug Co. Name: NOVY OIL & GAS, INC.  
Proposal Rcvd. from: KIRK GLENN OR DON MAY Company: NOVY OIL & GAS Phone: (620) 282-2212

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/15/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP @ 1700' - PERFS 1679 TO 1561, SPOTTED 10 SXS @ 1650', SPOTTED 45 SXS OF CEMENT @ 1550' - TAGGED TOC @ 1200'. PERFORATED CASING AT -900', & 275' WITH 4 SHOTS PER FOOT. RAN TUBING ITNO 880' SPOTTED 35 SXS CEMENT WAITED TWO HOURS, TAGGED TOC @ 600'. RAN TUBING INTO 275' CIRCUALTED TO SURFACE WITH 230 SXS OF CEMENT. CEMENT FELL BACK 60' INSIDE PIPE, AND 22' BETWEEN SURFACE CASING, CAPPED WITH 13 SXS CEMENT, ON 8/21/14.

Perfs:

Top	Bot	Thru	Comments
3645	3651		
1679	1681		
1568	1570		
1561	1570		

Received  
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING OUT OF GREAT BEND, TICKET #63709

SEP 05 2014

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

*B. J. Hope*

9.9.14 (TECHNICIAN)