

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21486-00-00
Spot: SESENE Sec/Twnshp/Rge: 29-23S-10W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: BENJES SOUTH Well #: 1
County: RENO Total Vertical Depth: 3850 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: PO BOX 559
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3850		150 SX
SURF	8.625	225		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/26/2014 12:00 AM
Plug Co. License No.: 31714 Plug Co. Name: NOVY OIL & GAS, INC.
Proposal Rcvd. from: KIRK GLENN Company: _____ Phone: (620) 282-2212

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 08/13/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3640'- CAPPED WITH 5 SXS CEMENT ON TOP. PERFORATED CASING AT 1450', -880', & -350' WITH 4 SHOTS PER FOOT. RAN TUBING INTO 1445' SPOTTED 35 SXS CEMENT, WAITED TWO HOURS TAGGED TOC @ 1250'. RAN TUBING INTO 880' SPOTTED 35 SXS CEMENT WAITED TWO HOURS, TAGGED TOC @ 650'. RAN TUBING INTO 350' CIRCULATED TO SURFACE WITH 300 SXS OF CEMENT. CEMENT FELL BACK 75' INSIDE PIPE, AND 15' BETWEEN SURFACE CASING, CAPPED WITH 11 SXS CEMENT, ON 8/21/14.

Perfs:

Top	Bot	Thru	Comments
3710	3711		

Received
KANSAS CORPORATION COMMISSION
SEP 05 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING OUT OF GREAT BEND, TICKET #63704

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

9.9.14CKM

JK