

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-21359-01-00  
Spot: NENENENE Sec/Twnshp/Rge: 4-17S-4W  
160 feet from N Section Line, 255 feet from E Section Line  
Lease Name: NEUSTROM Well #: 1-4H  
County: MCPHERSON Total Vertical Depth: 3641 feet

Operator License No.: 34923  
Op Name: PETROFLOW ENERGY CORPORATION  
Address: 525 S. MAIN ST., STE 1120  
TULSA, OK 74103

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 7     | 3986       |             | 350 SX   |
| SURF   | 9.625 | 275        |             | 130 SX   |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/16/2014 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Revd. from: CORKY GASTON Company: \_\_\_\_\_ Phone: (405) 831-7654

Proposed Plugging Method: Set bridge plug at approximately 3679' or maximum depth possible Cap with 6 sacks of cement Fill hole with drilling mud Pump cement surface plug from 30' to surface Cut cap and place ID plate on well CBL is the only open hole log run on this well.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/21/2014 4:00 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

SET CIBP @ 3679' ON 7/18/14. 7/21/14 TAGGED CIBP PLUG BACK TO 3200'. TOTAL OF 85 SXS CLASS A COMMON, PERF @ 550' 50 SXS CLASS TAGGED @ 370'. PERF @ 330' PUMPED 140 SXS CLASS A. TOTAL CEMENT 275 SXS CLASS A 2% CC. CEMENT DID CIRCUALTE. CHECKED PLUG 7/22/14 STAYED FULL.

Perfs:

Remarks: LOG TECH OF KANSAS TICKET #8067. CEMENT TICKET #48587. -- MTD = 5800

Plugged through: TBG

Received  
KANSAS CORPORATION COMMISSION  
**SEP 09 2014**  
CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed Jeff Klock  
9.9.14. ckm (TECHNICIAN)