

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-16540-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 2-18S-14W  
feet from Section Line, feet from Section Line  
Lease Name: EVELEIGH Well #: 2  
County: BARTON Total Vertical Depth: 3392 feet

Operator License No.: 7023  
Op Name: KLIMA WELL SERVICE, INC.  
Address: PO BOX 48  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3372		
SURF	8.625	185		125 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/11/2014 8:30 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA WELL SERVICE Phone: (620) 786-1031

Proposed Plugging Method: Ordered 380 sx 60/40 pozmix 4% gel cement, 10 sx gel and 400 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/11/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 1500', 890' and 220'.  
09/10/2014- Cleaned out to 1550' w/bit. Plugged up tubing and pulled out of hole.  
09/11/2014- Pumped down tubing with pump truck and circulated down to 1700'. Stacked out hard. Could not make any hole. Pulled tubing to 1696' and pumped 100 sx cement. Pulled tubing to 700' and pumped 100 sx cement. Cement circulated out the backside. POOH.  
Hooked to casing and pumped 90 sx cement w/150 # hulls. Lost circulation on braden head. Pressured up casing to 250 psi and shut in. Hooked to braden head and pumped 20 sx cement. Pressured up to 200 psi. Let stand for 15 minutes and pressure stayed.  
GPS: 38.50923 -098.84525

Received  
KANSAS CORPORATION COMMISSION

Remarks: QUALITY WELL SERVICE TICKET # 2651

SEP 23 2014

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Ray A. Dinkel  
(TECHNICIAN) CM

9/23/14 CRM

SEP 15 2014

Form CP-2/3