

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19439-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 22-10S-20W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SUTOR Well #: 1
County: ROOKS Total Vertical Depth: 3724 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2.875	3681		250 sx
PROD	4.5	3716		100 SX
SURF	8.625	160		90 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2014 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: 2 7/8" tubing cemented in. 4 1/2" casing w/250 sx cement. Top of cement at 475'. Squeezed job: 1400' - 1437' w/50 sx cement. Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/04/2014 11:50 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes at 450'. Swift Services pumped 75 sx cement circulated out 4 1/2" casing. Shut in 4 1/2" casing and pumped 225 sx cement w/300 # hulls down 2 7/8" tubing. Maximum pressure 300 psi. Shut in pressure 225 psi.

Perfs:

Remarks: SWIFT SERVICES TICKET # 26760

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

SEP 23 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

SEP 17 2014

9/13/14 CKM

Form CP-2/3