

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20377-00-00
Spot: SWSENE Sec/Twnshp/Rge: 24-15S-13W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: LUERMAN-PIESTER Well #: 2-3
County: RUSSELL Total Vertical Depth: 3340 feet

Operator License No.: 30606

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3230		75 SX
SURF	8.625	248		175 SX

Op Name: MURFIN DRILLING CO., INC.

Address: 250 N WATER STE 300

WICHITA, KS 67202

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/29/2014 9:30 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: STAN FROETSCHNER

Company: MURFIN DRILLING CO., INC.

Phone: (785) 483-1197

Proposed
Plugging
Method:
Ordered 350 sx 6/40 pozmix 4% gel cement, 11 sx gel and 300 # hulls.

Plugging Proposal Received By: RAY DINKEL

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/30/2014 3:00 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1500', 825', 450' and 250'. Ran tubing to 3050' and pumped 11 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 100 sx cement. Pulled tubing to 500' and pumped 50 sx cement. Cement circulated out backside. POOH. Hooked to casing and pumped 25 sx cement at 300 psi. Shut in. Hooked to braden head and pumped 25 sx cement at 350 psi.

Topped off with redi mix.

GPS: 38.73389 -098.71106

Perfs:

Top	Bot	Thru	Comments
3122	3128		
3112	3118		
3096	3100		
3066	3072		

Received
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING TICKET # 55483


SEP 23 2014

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed



(TECHNICIAN)

9/23/14 CRM

CM

SEP 23, 2014