

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-24038-00-01
Spot: SENWSWNW Sec/Twnshp/Rge: 22-9S-24W
1797 feet from N Section Line, 490 feet from W Section Line
Lease Name: STEVE NICKELSON Well #: 22-1
County: GRAHAM Total Vertical Depth: 4394 feet

Operator License No.: 6861
Op Name: RON'S OIL OPERATIONS INC
Address: 1889 200TH AVE
PENOKEE, KS 67659

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
PROD	4.5	4394		220 SX
SURF	8.625	210		165 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/02/2014 11:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC. Phone: (785) 475-7218

Proposed
Plugging
Method:

Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations at 4291' - 4295', 4047' - 4050', 4031' - 4034' and 3881' - 3885'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2014 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Pioneer perforated at 2170', 1015' and 260'. Ran tubing to 3906' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 2175' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1040' and pumped 200 sx cement to circulate cement to surface. 8 5/8" x 4 1/2" annulus also circulated. Pulled all tubing. Topped off 4 1/2" casing and 8 5/8" x 4 1/2" annulus w/40 sx cement.

GPS: 39.25758N -099.99455W

Remarks: GLOBAL CEMENTING TICKET # 1430

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

SEP 18 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed _____

Pat Bedore

9/23/14 CKM

(TECHNICIAN)

CM

Form CP-2/3

SEP 05 2014