

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21402-00-00
Spot: W2SWSE Sec/Twnshp/Rge: 9-9S-20W
660 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WHISMAN Well #: 3
County: ROOKS Total Vertical Depth: 3698 feet

Operator License No.: 9957
Op Name: THOMASON PETROLEUM, INC
Address: 2717 CANAH BLVD. PO BOX 875
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3697		125 SX
SURF	8.625	210		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/11/2014 11:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: STEVEN THOMASON Company: THOMASON PETROLEUM, INC. Phone: (785) 625-9045

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: PAT BEDORE Witness Type: NONE
Date/Time Plugging Completed: 08/11/2014 2:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 2250', 1650', and 950'. Ran tubing to 3360' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1560' and pumped 90 sx cement to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/35 sx cement. Hooked to 8 5/8" x 4 1/2" annulus. Pressured immediately.

Perfs:

Top	Bot	Thru	Comments
3689	3691		
3683	3685		
3462	3464		
3444	3446		
3424	3426		
3370	3373		

Remarks: ALLIED TICKET # 55396

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

SEP 18 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Pat Bedore
(TECHNICIAN)

9/23/14 ckm

CM

SEP 02 2014