

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20983-00-00  
Spot: SENE SW Sec/Twnshp/Rge: 6-9S-17W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: MOOS Well #: 1  
County: ROOKS Total Vertical Depth: 3400 feet

Operator License No.: 5399  
Op Name: TREK AEC, LLC  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3398		150 SX
SURF	8.625	172		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/10/2014 9:30 PM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: THAD STARR Company: TREK AEC, LLC Phone: (620) 793-2146

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
CIBP at 3100'. Production perforations: 3384' - 3387'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/10/2014 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1900', 1280', 600' and 200'. Ran tubing to 3052' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2050' and pumped 80 sx cement w/100 # hulls. Pulled tubing to 1280' and pumped 150 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/25 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Shut in pressure 200 psi.

GPS: 39.29670N -099.26173W

Perfs:

Top	Bot	Thru	Comments
3384	3387		

Received  
KANSAS CORPORATION COMMISSION

Remarks: GLOBAL CEMENTING TICKET # 1453

Plugged through: TBG

SEP 23 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

Pat Bedore

9/23/14 ckm

(TECHNICIAN)

CM

SEP 18 2014

Form CP-2/3