

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22572-00-00
Spot: C SW Sec/Twnshp/Rge: 5-34S-14W
1295 feet from S Section Line, 1270 feet from W Section Line
Lease/Unit Name: DAVIS RANCH A Well Number: 1
County: BARBER Total Vertical Depth: 5440 feet

Operator License No.: 5506 Conductor Pipe: Size 10.75 feet: 220
Operator Name: WOOLSEY PETROLEUM CORPOR Surface Casing: Size 8.625 feet: 856
Address: 125 N. MARKET, SUITE 1000 Production: Size 4.5 feet: 5427 176.80
WICHITA, KS 67202 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/03/2000 1:30:00 PM

Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.

Proposal Rcvd. from: ALAN DICK Company: WOOLSEY PETROLEUM Phone: (316) 267-4379

Proposed Plugging Method: DOWN SURFACE CASING PUMP, 300# COTTONSEED HULLS, 10 SX GEL., 50 SX 60 POZMIX, 10 SX GEL., 100# COTTONSEED HULLS, 1-8 5/8" WIPER PLUG AND 150 SX SANE CEMENT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/03/2000 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

BASKET WAS RUN & TOP OF 8 5/8" SURFACE PIPE WAS CEMENTED WITH 25 SX CMT. PERFS AT 5262-5269'. SET CIBP @ 5210' AND PUT 2 SX CMT ON TOP OF CIBP. PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS & 150 SX CMT. MAXIMUM PRESSURE 650#. SHUT IN PRESSURE 500#. 8 5/8" SURFACE PIPE COLLAR BAD. PLATED & PUT IN 5 1/2" COLLAR TO PUMP DOWN. LEFT OUT 8 5/8" WIPER PLUG.

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 2000

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4792' OF 4 1/2" CASING.

10-27-00
CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 10/30/00 OCT 05 2000

INV. NO. 2001060899MP

Form CP-2/0