

To: 1 040553
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-23
API NUMBER 19- 151-21,898 -00-00 236P

SE NE NW, SEC. 8, T 27 S, R 11 WXX
4290 feet from S section line
2820 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5929
Operator: A. & A Discovery, Inc.
Name & Address: P.O. Box 156
Hill City, KS 67642

Lease Name Holland Well # B-1
County Pratt 130.74
Well Total Depth 4023 feet
Conductor Pipe: Size 10 3/4 feet 263
Surface Casing: Size 8 5/8 feet 762

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 8:45 a.m. Day: 17 Month: 7 Year: 19 91

Plugging proposal received from Bruce Wagner
(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 3996' w/150 sx cement, Perfs at 3810-14, 3975-79, 3704-07'
1st plug sand back to 3760' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN) Wichita, Kansas
1111 29 1991

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 12:30 p. Day: 23 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3617' and dumped 4 sx cement on top of
sand bridge through bailer,
7/17/91 2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx
cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 900 psi and shut in 450 psi. 7/23/91 3rd plug pumped down 8 5/8" X 10 3/4"
annulus w/150 sx cement. Maximum pressure 100 psi and shut in 0 psi.
No vacuum on annulus when job completed.

Remarks: Used 60/40 Pozmix, 6% gel by B.J. Services. Recovered 2334' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-12-91
INV. NO. 32657

Signed Stephen J. Difer (TECHNICIAN)