

1 120336

11-2

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,953-00-00

TECHNICIAN'S PLUGGING REPORT

App. SW NE SW, SEC. 8, T 27 S, R 11 W/E
1660 feet from S section line
3660 feet from E section line

Operator License # 4748
Operator: A & A Discovery, Inc.
Name & Address P.O. Box 156
Hill City, KS 67642

Lease Name Holland Well # A-5
County Pratt 131.30
Well Total Depth .4040 feet
Conductor Pipe: Size 10 3/4 feet 247
Surface Casing: Size 8 5/8 feet 747

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929
Address 310 West Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 8 a.m. Day: 2 Month: 11 Year: 1989

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 576'

- 1st plug at 780' with 50 sx cement,
- 2nd plug at 400' with 40 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 2 Month: 11 Year: 19 89

- ACTUAL PLUGGING REPORT 1st plug at 780' with 50 sx cement,
- 2nd plug at 400' with 40 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 6 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

(Do not) observe this plugging.

INVOICED

DATE 11-7-89

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 26373
11-2