

1 040552

7-24

237p

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,990-00-00  
21' E of C-of  
SW NE NW, SEC. 8, T 27 S, R 11 W/8

4290 feet from S section line  
3609 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5929

Lease Name Holland Well # B-2

Operator: A & A Discovery Inc.

County Pratt 130.84

Name & Address P.O. Box 156

Well Total Depth 4026 feet

Hill City, KS 67642

Conductor Pipe: Size 10 3/4 feet 271

Surface Casing: Size 8 5/8 feet 757

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:15 a.m. Day: 17 Month: 7 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4020' w/100 sx cement, Perfs at 3912-18, 3950-54'

1st plug sand back to 3860' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls

release 8 5/8" wiper plug and pump 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

III 29 1991

Plugging Proposal Received by Steve Middleton (TECHNICIAN) CONSERVATION DIVISION  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:30 a.m. Day: 24 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3682' and dumped 4 sx cement on top of

hulls sand bridge through bailer, 2nd plug 7/17/91-Pumped down 8 5/8" surface pipe with 300 lbs. and 10 sx gel. 8 5/8" surface pipe lifted out of hole approx. 30' w/a max. of 100 psi.

8 5/8" s.p. fell back in hole. Shut down. 8 5/8" is parted.

7/23/91-Spotted the following plugs in 8 5/8" surface pipe through 2 3/8" tubing:

1st plug at 778' w/50 sx cement, 2nd plug at 344' w/25 sx cement-B.J. w/60/40 Pozmix 3% cc.

Laid tubing down. Pulled out and laid down 1 jt. 8 5/8" s.p.(42'). Shut down.

7/24/91-Tagged top plug w/2 3/8" tubing at 280'. Laid down tubing. Pumped down 10 3/4"

conductor pipe (for 8 5/8" X 10 3/4" annulus and surface plug) w/150 sx 60/40 Pozmix 6% gel.

Maximum pressure 200 psi and shut in 190 psi.

Remarks: Cemented by B.J. Services. Recovered 3006' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED  
(If desired, check here to observe this plugging.)

DATE 8-12-91

Signed *Stephen J. Duffer* (TECHNICIAN)

INV. NO. 32658