

1 060953

APR 24 1987

163

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21, 681-00-00  
NW NW NW, SEC. 6, T 27 S, R 11 W E  
4950 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038

Lease Name Hoover "A" Well # 1

Operator: Robinson Oil Company

County Pratt

Name & Address 737 R.H. Garvey Building

Well Total Depth 4435 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 7:30 a.m. Day: 24 Month: 4 Year: 19 87

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4416' PBTD 3800' Perfs at 3707-11, 3842-44', 4129 1/2-4146 1/2'

1st plug sand back to 3660' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 'sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant and Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9 a.m. Day: 24 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3660' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Recovered 3275' of 4 1/2" casing RECEIVED 60/40 Pozmix 4% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

APR 28 1987

DATE 4-29-87

CONSERVATION DIVISION  
Wichita, Kansas

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 16674