

1 051816

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-24

API NUMBER 15-033-70272-0000

C NE NE, SEC. 17, T 35 S, R 16 W  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9723

Lease Name McMoran Well # 2

Operator: DoMar Oil & Gas, Inc.

County Comanche

Name: P.O. Box 238

Well Total Depth 5378 174.78

Address Liberal, KS 67905-0238

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 494

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1 p.m. Day: 24 Month: 6 Year: 1994

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

vera: 4 1/2" at 5374' w/200 sx cement, Perfs at 5033-42, 5203-11, 5307-14'

1st plug pump 2 sx hulls and 25 sx cement on bottom,

2nd plug pump 50 sx cement at 1200',

3rd plug pump 40 sx cement at 500',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 24 Month: 6 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement on bottom,

2nd plug pumped 50 sx cement at 1200',

3rd plug pumped 40 sx cement at 520',

4th plug pumped 10 sx cement at 40'.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 29 1994

Remarks: Used common cement by Sargent's. Recovered 3560' of 4 1/2" casing.

INVOICED  
(if additional description is necessary, use BACK of this form)  
(did / observe) observe this plugging.

DATE 6-29-94

Signed Richard M. Lacey  
(TECHNICIAN)

INV. NO. 40703

6-24