

To: 1 051562
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-14 API NUMBER 15-151-20,963-00-00 220 R

SW SW, SEC. 31, T. 26 S, R. 15 W/E
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364
Operator: Beren Corporation
Name & Address: P.O. Box 723
Hays, KS 67601

Lease Name Fish & Game Well # 1-31
County Pratt 146.64
Well Total Depth 4512 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 464

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 9:30 a.m. Day: 14 Month: 7 Year: 19 92

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 4511' w/250 sx cement, Perfs at 4252-57, 4450-60'

1st plug set CIBP at 4175' and dump 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 14 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4175' and dumped 2 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2418' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
I did observe this plugging.

DATE 8-10-92
INV. NO. 35904

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1992
CONSERVATION DIVISION
WICHITA, KANSAS