

1090211

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,989 -00-00

NE NE SE, SEC. 22, T 26 S, R 15 (W) X  
N SE Corner of  
2310 feet from NXX section line  
W SE Corner of  
330 feet from NXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Curtis Well # 1

Operator: Vincent Oil Corporation

County Pratt

Name & Address 125 N. Market, Suite 1110

Well Total Depth 4433 144.07 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 419

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 27 Month: July Year: 19 84

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4260' Perfs 3917-21' CIBP at 4000'

1st plug sand back to 3860' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 125 sx cement.

Plugging Proposal Received by R. Barluttan (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 pm Day: 27 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4260' Perfs 3917-21' CIBP at 4000'

1st plug sanded back to 3860' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

AUG 01 1984

Remarks: They recovered 2413' of 4 1/2" casing. Cemented by Sun

(If additional description is necessary, use BACK of the CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 8-4-84

Signed R. Barluttan (TECHNICIAN)

INV. NO. 2860