

1 030395

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,082-00-00

C S/2 NW, SEC. 36, T 26 S, R 15 W/EX

3300 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Lutes Well # 1-36

Operator: Texas Energies, Inc.

County Pratt 153.92

Name & Address P. O. Box 947

Well Total Depth 4736 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 406

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 346, Chase, KS 67524

Company to plug at: Hour: 4:00 pm Day: 9 Month: April Year: 1985

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 816-938-2457

were: 4 1/2" at 4690' PBD 4470' Perfs at 4485-4490' 4596-4501' 4394-4404'

1st plug pump 2 sx hulls and 50 sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 5:30 pm Day: 9 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 50 sx cement to bottom,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

APR 12 1985

Maximum pressure 500 psi and shut in 50 psi

CONSERVATION DIVISION Wichita, Kansas

Remarks: Recovered 2000' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-18-85

INV. NO. 7784

Signed Steve Durrant (TECHNICIAN)