

To: 1 070049
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15-151-21,562-00-00
45' N of
C W/2 SW, SEC. 35, T 26 S, R 15 W/4E
1365 feet from S section line
4620 feet from E section line

Operator License # 5030
Operator: Vess Oil Corporation
Name & Address: 8100 E. 22nd St. N, Bldg. 300
Wichita, KS 67226

Lease Name Stotts Well # 1-35
County Pratt 147.87
Well Total Depth 4550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 483

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 12:40 P.m. Day: 27 Month: 11 Year: 19 96

Plugging proposal received from Manny
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 4 1/2" at 4548' w/150 sx cement, PBD 4500', Perfs at 4412-17, 4435-40, 4457-67'
1st plug pump 20 sx cement and 1 sx hulls to 4200',
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:15 p.m. Day: 27 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement and 1 sx hulls to 4200',
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 550 psi and shut in 250 psi.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 03 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2352' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)
CONSERVATION DIVISION WICHITA, KS

INVOICED
I () did not observe this plugging.

DATE DEC 05 1996

Signed [Signature] (TECHNICIAN)

INV. NO. 47113