

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,562-00-00

LEASE NAME Stotts

WELL NUMBER 1-35

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 35 TWP. 26 RGE. 15W (E) or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 11-22-96

Plugging Completed 11-27-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 East 22nd St. N, Bldg 300 Wichita, KS 67226

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	483'	none
				4 1/2	4548'	2050'

RECEIVED
KANSAS
CORPORATION
COMMISSION
NOV 27 11 11 AM '96

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each side. Pumped bottom with 200# hulls followed by 20 sks common cement. Displaced plug to 3673' & pressured to 1500#. Shot well at 2721', worked pipe. Shot at 2416', worked pipe. Shot at 2050', worked pipe free. Pulled out all pipe. Plugged well with 300# hulls, 10 gel, 50 cement, 10 gel, 100# hulls, release plug, mix 150 sks cement. Shut in at 250# psi. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 96

Gene L. Bergberg
Notary Public

My Commission Expires:

