

1 060153

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE SW SE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,412 -00-00

SEC. 14 , T 26 S, R 15 W/E

330 feet from N/S section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Smith '0-0' Well # 1

Operator: Pickrell Drilling Company

County Pratt

Name & Address 110 North Market, Suite 205

Well Total Depth 4575 148.68 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 408 KB

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company License Number 5123

Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 9 Month: February Year: 19 84

Plugging proposal received from Herb French

(company name) Pickrell (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 900' with 50 sx cement

2nd plug at 450' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement
plug water well with 5 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 :15 Day: 9 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 900' with 50 sx cement, 2nd plug at 450' with 50 sx
cement. 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement. 5th plug to circulate rathole with 15 sx cement. Plug water well with
5 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc. by Allied Ticket No. 41392

INVOICED

(additional description is necessary, use BACK of this form.)

DATE 2-22-84 I (did / did not) observe this plugging.

INV. NO. 0304

Signed Paul A. Luthi
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1984
CONSERVATION DIVISION
Wichita, Kansas