

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,312-00-00

~~SE/4~~ SEC. 8, T. 26S, R. 15W

1650 FEET FROM ~~N/S~~ SECTION LINE

TECHNICIAN'S PLUGGING REPORT

330 FEET FROM ~~NE~~ SECTION LINE

OPERATOR LICENSE # 7444

LEASE NAME CURTIS "A" WELL # 2

OPERATOR: WTA ENERGY, INC
NAME & ADDRESS P.O. Box 30159
AMARILLO, TX 79120

COUNTY Pratt

WELL TOTAL DEPTH 4702 \$152.82 FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8 FEET 350

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR WTA DRILLING INC. LICENSE NUMBER 7443

ADDRESS P.O. Box 30159, Amarillo, TX 79120

COMPANY TO PLUG AT: HOUR: 11 pm DAY: 9 MONTH: Aug. YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM Bernie Burdge

(COMPANY NAME) W-T-A, DRILLING (PHONE) _____

WERE: to use 60/40 Pozmix w/2% gel & 3% CaCl AND

Set 1st plug @ 930' w/50 sf

2nd plug @ 390' w/40 sf

3rd plug @ 40' w/solid bridge & 10 sf to surface

Circulate 15 sf in rat hole & 10 sf in mouse hole w/5 sf

in water well. PLUGGING PROPOSAL RECEIVED BY R. Barluttan
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 3:25 AM DAY: 10 MONTH: Aug YEAR: 19 83

ACTUAL PLUGGING REPORT plugged as proposed.

Cementing by Halliburton

REMARKS: Cement ticket # 697256

I (~~did~~ / DID NOT) OBSERVE THIS PLUGGING.

RECEIVED SIGNED
STATE CORPORATION COMMISSION

R. Barluttan
(TECHNICIAN)

AUG 18 1983

INVOICED

DATE 8-19-83

INV. NO. 5284-W

FORM CP-2/3
REV. 6-83

Wichita, Kansas