

To: 1 040402  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA  
NW/4, SEC. 6, T 26 S, R 15 (W) BK  
feet from S section line  
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9158  
Operator: Case Oil & Gas  
Name & Address: P.O. Box 8564  
Pratt, KS 67124

Lease Name Goertz Well # 1  
County Pratt 145.05  
Well Total Depth 4463 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 60501

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 6 Month: 2 Year: 1990

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4460' Perfs at 4375-95'

1st plug sand back 50' above perfs and top with 5 sx cement,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1 p.m. Day: 6 Month: 2 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 4325' and dumped 5 sx cement with bailer  
on top of sand bridge,  
2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 650 psi and shut in 300 psi.

Remarks: Used 60/40 oz mix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
FEB 13 1990

observe this plugging.

Signed Stephen J. Pfeiffer  
(TECHNICIAN)

DATE FEB 14 1990

INV. NO. 27422