

1 030616

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,749-60-00
Odd Section
NW NW, SEC. 4, T 26 S, R 15 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047

Lease Name Hart Well # 1

Operator: Rupe Oil Company, Inc.

County Pratt

Name & Address P. O. Box 2273

Well Total Depth 4650 Simpson 151.13 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Union Drilling Company, Inc. License Number 5103

Address 422 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 6:45 pm Day: 15 Month: December Year: 19 85

Plugging proposal received from Gib Overby

(company name) Union (phone) 316-262-1872

Elevation N/A

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1028-06'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 330' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement. Plug water well from bottom to top with cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:00 pm Day: 15 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1028' with 50 sx cement, 2nd plug at 330' with 40 sx cement,

3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton #351863-6

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

STATE CORP.

Signed

Steve Durrant

(TECHNICIAN)

DATE DEC 20 1985

DEC 20 1985

INV. NO. 11684

CONSERVATION DIVISION

FORM CP-2/3
Rev. 01-84