

No: 1 040689  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-17 API NUMBER 15-151-20,313-~~000~~20 R

NW NW SW, SEC. 29, T. 26 S, R 12 W/E  
2310 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5015  
Operator: Hellar Drilling Company, Inc.  
Name & Address 125 N. Market  
Wichita, KS 67202

Lease Name Stueder Well # 5  
County Pratt 103.77  
Well Total Depth 3193 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 293

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111  
Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 17 Month: 8 Year: 19 92  
Plugging proposal received from Deacon Pulley  
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 7" at 3192' w/225 sx cement, PBTB 3154', Perfs at 3137-41'  
1st plug sand back to 3090' and dump 7 sx cement on top of sand bridge through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"  
wiper plug and pump 150 sx cement.

\_\_\_\_\_ Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10 a.m. Day: 17 Month: 8 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 3080' and dumped 6 sx cement on top of sand  
bridge through bailer,  
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, and 150 sx cement.  
Maximum pressure 100 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1616' of 7" casing.  
(If additional description is necessary, use BACK of this form.)  
Wichita, Kansas

STATE CORPORATION COMMISSION  
RECEIVED  
AUG 24 1992  
8-24-92  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**  
I (did ~~not~~) observe this plugging.  
DATE 8-27-92  
NO. 36070

Signed Stephen J. Phipps  
(TECHNICIAN)