

To: 1 040475  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5015

Operator: Hellar Drilling Company, Inc.  
Name &  
Address 125 N. Market, #1422  
Wichita, KS 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 22 Month: 10 Year: 19 90

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4303' w/150 sx cement, PBD 4266', Perfs at 4192-98'

1st plug sand back to 4140' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10 a.m. Day: 22 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4140' and dumped 5 sx cement on top of  
sand bridge through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1715' of 5 1/2" casing.

(If additional descriptions are necessary, use BACK of this form.)

**INVOICED**

DATE 11-5-90

INV. NO. 298.23

RECEIVED  
OCT 30 1990  
10-30-90  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Stephen J. Pfeiffer  
(TECHNICIAN)

FORM CP-2/3  
Rev. 01-84