

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20744-00-00  
Spot: SESWSENW Sec/Twnshp/Rge: 1-1S-19W  
2870 feet from S Section Line, 1945 feet from W Section Line  
Lease Name: KARON Well #: 1  
County: PHILLIPS Total Vertical Depth: 3441 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		175 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2014 12:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: TONY Company: MURFIN DRILLING CO., INC. Phone: (785) 443-2415

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY Witness Type: NONE  
Date/Time Plugging Completed: 09/09/2014 3:45 PM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @1670 w/50 sx  
2nd plug @1125 w/100 sx  
3rd plug @270 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

Received  
KANSAS CORPORATION COMMISSION

SEP 23 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

*Chris Neeley*

(TECHNICIAN)

9.23.14 ckm

CM

SEP 18 2014

Form CP-2/3