

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21605-00-01  
Spot: S2SENWNW Sec/Twnshp/Rge: 10-10S-25W  
4120 feet from S Section Line, 4321 feet from E Section Line  
Lease Name: ELRICK UNIT Well #: 11-4A  
County: GRAHAM Total Vertical Depth: 4143 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4133		350 SX
SURF	8.625	268		250 SX

Well Type: EOR UIC Docket No: E21970.1 Date/Time to Plug: 09/10/2014 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: SANDRA GONCALVES Company: CITATION OIL & GAS Phone: (281) 891-1555

Proposed Plugging Method: 8 5/8" surface casing set at 268' w/250 sx cement. 5 1/2" production casing set at 4133' w/350 sx cement. DV Tool set at 2332' w/400 sx cement. Perforations: 3784' - 3790', 3795' - 3799', 3832' - 3836', 3938' - 3944', 3984' - 3990' and 4009' - 4014'. TD 4143'. PBT 4093'

Ordered 400 sx 60/40 pozmix 4% gel cement, 11 sx gel and 150 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/10/2014 10:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Ran tubing to 3780'. Tagged fill up. Pulled tubing to 3720' and pumped water and 6 sx gel. Tubing pressured and could not pump into. Pulled tubing to surface. Iron sulfide plug in bottom of tubing jnt. Ran tubing to 3685'. Displaced tubing volume with water. Pumped 5 sx gel and followed with 80 sx cement w/150 # hulls. Pulled tubing to 2400' and pumped 125 sx cement. Pulled tubing to 1200' and pumped 140 sx cement. Cement to surface. Pulled tubing to surface and topped off 5 1/2" casing w/20 sx cement. Connected to 8 5/8" surface casing. Pumped 10 sx cement and pressured to 275 psi.

GPS: 39.20121N -100.10423W

Remarks: ALLIED CEMENT TICKET # 63,522

Plugged through: TBG

Received  
KANSAS CORPORATION COMMISSION

SEP 23 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Darrel Dipman  
cc: uic (TECHNICIAN) CM

9/23/14 ocm

SEP 17 2014