

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20828-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 11-14S-15W  
3630 feet from S Section Line, 990 feet from E Section Line  
Lease Name: DUMLER C Well #: 7  
County: RUSSELL Total Vertical Depth: 3302 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S YALE # 702  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3299		125 SX
SURF	8.625	231		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2014 9:00 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY, INC. Phone: (620) 282-9034

Proposed  
Plugging  
Method:

Ordered 325 sx 60/40 pozmix 4% gel cement, 400 # hulls and 10 sx gel.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/09/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

08/29/2014- Squeezed holes at 396' - 1024' and pumped 200 sx of CL A 3% C.C. Drilled out and the bottom did not hold. Drilled out CIBP.  
09/09/2014- Perforated at 220' and 1400'. Ran tubing to 3105' and pumped 9 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 100 sx cement. Pulled tubing to 450' and pumped 75 sx cement. Circulated cement out backside. POOH. Hooked to casing and pumped 40 sx cement. Cement circulated out braden head. Shut in and pressured casing to 350 psi. Shut in.

GPS: 38.85175 -098.95052

Perfs:

Top	Bot	Thru	Comments
3299	3302		
3074	3236		

Remarks: GLOBAL CEMENTING TICKET # 1437

Plugged through: TBG

Received  
KANSAS CORPORATION COMMISSION

SEP 23 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

*Ray A. Dinkel*

(TECHNICIAN)

CM

9/23/14 cpm

SEP 17 2014