

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23719-00-00
Spot: NESENWSE Sec/Twnshp/Rge: 28-13S-15W
1759 feet from S Section Line, 1370 feet from E Section Line
Lease Name: ROHLEDER Well #: 1
County: RUSSELL Total Vertical Depth: 3407 feet

Operator License No.: 34259
Op Name: JAG OPERATIONS, INC.
Address: 710 S. FRONT PO BOX 628
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3400		150 SX
SURF	8.625	239		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/08/2014 8:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: JACK YOST Company: JAG OPERATIONS, INC. Phone: (785) 483-0271

Proposed
Plugging
Method:

Ordered 500 sx 60/40 pozmix 4% gel cement, 18 sx gel and 400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/08/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked up to casing and pumped 50 sx cement w/100 # hulls followed by 12 sx gel, followed by 225 sx cement w/300 # hulls. Shut down and WOC. Pumped an additional 45 sx cement and squeezed a 500 # psi. Pumped 320 sx cement. Braden head was dug and found to be full of cement.

GPS: 38.89028 -098.98827

Perfs:

Top	Bot	Thru	Comments
3351	3354		
3274	3276		
3251	3253		
3186	3188		

Received
KANSAS CORPORATION COMMISSION

SEP 23 2014

Remarks: GLOBAL CEMENTING TICKET # 1435

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

9/23/14 OPM

SEP 12 2014

Form CP-2/3