

To: 1-040608 15-151-10650-0000  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

AP: NUMBER 15-13-92 Drill Completion Date 1957 502  
NE NE SE, SEC. 30, T. 26 S, R. 12 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

Operator: Knighton Oil Company  
Name & Address 710 Petroleum Bldg.  
Wichita, KS 67202

2310 feet from S section line  
330 feet from E section line

Lease Name Petrowsky Well # 1A  
County Pratt 139.36

Well Total Depth 4288 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 2 p.m. Day: 13 Month: 1 Year: 19 92

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: 5 1/2" at 4287' w/125 sx cement, PBTB 4255', Perfs at 4218-25, 4117-25, CIBP at 4060'  
Perfs 3697-3704', squeezed from 3296-2800'

1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 p.m. Day: 13 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3000' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 250 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1916' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE JAN 29 1992

INV. NO. 34407

Signed Stephen J. Pifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1992  
1-16-92  
CONSERVATION DIVISION  
WICHITA, KS