

To: 1 040609  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-13-92  
API NUMBER 15-151-20,396-0000 514  
NW NW SE, SEC. 30, T. 26 S, R. 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

Operator: Knighton Oil Company, Inc.

Name &

Address 710 Petroleum Bldg.

Wichita, KS 67202

2310 feet from S section line

2310 feet from E section line

Lease Name Petrowsky Well # 2A

County Pratt 103.35

Well Total Depth 3180 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 13 Month: 1 Year: 19 92

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: 4 1/2" at 3155' w/250 sx cement, PBSD 3140', Perfs at 3104-08, CIBP at 3025',

Perfs at 2404-09'

1st plug sand back to 2350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by \_\_\_\_\_ Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:15 p.m. Day: 13 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 2345' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1767' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

KANSAS CORPORATION COMMISSION

DATE JAN 29 1992

Signed Stephen J. Pifer  
(TECHNICIAN)

INV. NO. 34408

JAN 16 1992

1-16-92

CONSERVATION DIVISION