

To: 1 040732 1-15
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-151-10009-00-01 133
API NUMBER 15-Drill Completion Date 8/26/43
SW NW SE, SEC. 30, T 26 S, R 12 W/E
1650 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5015

Lease Name Petrowsky B Well # 2
County Pratt

Operator: Hellar Drilling Company, Inc.
Name:
Address 125 N. Market, Ste. 1422
Wichita, KS 67202

Well Total Depth 4316 140.27 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 827

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hellar Drilling Co. License Number 5015

Address 125 N. Market, Ste. 1422, Wichita, KS 67202

Company to plug at: Hour: 10:45 a.m. Day: 15 Month: 1 Year: 1993

Plugging proposal received from Russell Bright

(company name) Hellar Drilling Co. (phone) 316-267-2845

were: 4 1/2" at 4288' w/850 sx cement, PBD 3220', Perfs at 3062-68'

1st plug fill with 65/35 8% gel, check backside.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 15 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pump down 4 1/2" casing with 300 lbs. hulls ahead of cement and 300 lbs. in with first of a total of 250 sx cement, Maximum pressure 500 psi and shut in 420 psi. 2nd plug tied into 4 1/2" X 8 5/8" annulus and pumped down annulus with 100 lbs. hulls in with 20 sx cement. Maximum pressure 200 psi and shut in 160 psi. 4 1/2" had been cemented to surface.

RECEIVED
STATE CORPORATION COMMISSION
1-21-93
JAN 21 1993
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

Signed Stephen J. Pifer (TECHNICIAN)

If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE FEB 22 1993

CALL NO. 37400