

1 080427

API NUMBER 15- 151-21,115-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW NE NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEC. 10, T 26 S, R 12 W/EX
4290 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8778

Lease Name Enex-Clark Well # 1

Operator: Name & Address
Midwestern Supply Co., Inc.

County Pratt 140.89

Address 300 Patton Road

Well Total Depth 4335 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 417

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 8778

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 5:00 pm Day: 4 Month: October Year: 19 85

Plugging proposal received from Mark McCabe

(company name) Kelso (phone) 316-938-2941

were: 4 1/2" at 4334' Perfs at 4285-87'

1st plug sand back to 4235' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:00 pm Day: 4 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4235' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

STATE CORPORATION COMMISSION
OCT 15 1985
10-15-85
CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 200 psi and shut in 50 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3023' 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.

DATE 10-16-85

Signed J. A. [Signature] (TECHNICIAN)

INV. NO. 10611

Electra Log Inc.

Sec. 10 Twp. 26S Rcd. 12W
*Radiation Guard
Log*

*H. J. [unclear]
2/24/85*

COMPANY ENERGY EXPLORATION, INC.
WELL ENEX-CLARK #1
FIELD PETROWSKY EXT
COUNTY PRATT STATE KANSAS

Location SW NE NW Other Service
Sec. 10 Twp. 26S Rcd. 12W

Permanent Datum GROUND LEVEL Elev. 1873'
Log Measured From K.B. FIVE Elev. K.B. 1878'
Drilling Measured From KELLY BUSHING Elev. D.I. 1875'
G.I. 1873'

Date 3-26-82
Run No ONE
Depth - Driller 4335'
Depth - Logger 4332'
Btm Log Inter 4338'
Top Log Inter 0
Casing - Driller 8 5/8" 41 1/2"
Casing - Logger
Bit Size 7 7/8
Type Fluid in Hole STARCH
Dens. Visc. 9.8 48
pH Fluid Loss ml ml ml
S.G. of Sample FLOLINE
S. a Meas. Temp .36 a 48 l a l a
R. g Meas. Temp .27 a 48 l a l a
K. a Meas. Temp .54 a 48 l a l a
S.G. R. R CHARTS
R. a BHI .14 a 119 l a l a
Time Spent 2 HOURS
May Rec. Exp. 119
Equip. Location 140 GREAT BEND
Recorded By D. HERMAN
Witnessed By MR. THOMAS

STATE CORPORATION COMMISSION
AUG 22 1985
8-22-85
CORPORATION DIVISION
Topeka, Kansas