

1 040577

10-11

76 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 151-20.780-~~CS-01~~

C. NE SW, SEC. 10, T 26 S, R 12 WXX

1980 feet from S section line

3300 feet from E section line

Lease Name Schwertfeger Well # 1-10

County Pratt 141.53

Well Total Depth 4355 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 374

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893

Operator: Pratt Well Service, Inc.

Name & Address P.O. Box 847

Pratt, KS 67124

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:30 a.m. Day: 11 Month: 10 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 4349' w/160 sx cement, Perfs at 4110-20, 4082-92'

1st plug sand back to 3756' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:15 a.m. Day: 11 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3756' and dumped 5 sx cement on top of

sand bridge through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls and 100 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1816' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1991
10-15-91

INVOICED
observe this plugging.

DATE 11-4-91

INV. NO. 33568

Signed Stephen J. Hulse (TECHNICIAN)

15-151-20780-00-01



**ACOUSTIC CEMENT
BOND LOG**

COMPANY STUDIER OIL COMPANY WELL SCHWERTFERGER NO. 1 FIELD COUNTY PRATT STATE KANS	COMPANY .. STUDIER OIL COMPANY ..	10-7-91 OCT-07-1991
	WELL .. SCHWERTFERGER NO. 1 ..	
	FIELD ..	
	COUNTY .. PRATT .. STATE .. KANSAS ..	DIVISION ..
API No	Other Services	
Location	C - NE - SW	
Sec 10 Twp 26S Rge 12W		

Permanent Datum	GROUND LEVEL	Elev	1880'	Elev. KB	1892'
Log Measured From	KELLY BUSHING 12	Ft Above Perm. Datum		DF	1889'
Drilling Measured From	KELLY BUSHING			GL	1880'

Date & time Logged	9-11-85	Type of Fluid in Hole	WATER
Run No.	ONE	Density of Fluid	
Depth Driller	4350'	Fluid Level	FULL
Depth Logger		Cement Top Est	Logged 3250'
Btm Logged Interval	4248'	Equipment-Location	2081 PRATT
Top Logged Interval	3000'	Recorded By	T. COLE
Max Temp °F		Witnessed By	MR. B. STUDER

CEMENTING DATA	Surface String	Protection String	Production String	Liner
Date/Time Cemented			9-10-85	
Primary/Squeeze			SQUEEZE	
Expected	psi	psi	psi	psi
Comp Strength				
Cement Volume			150 SKS.	
Cement Type/Weight			COMMON	
FORMULATION			10/ CA-CL ₂	

Mud Type Mud Wt

BOREHOLE RECORD				CASING & TUBING RECORD			
Run No	Bit	From	To	Size	Wgt	From	To
	12 1/4"	0	380'	8-5/8"		0	380'
	7-7/8"	380'	T.D.	5 1/2"		0	T.D.

Part Number 26127

Page 1 of 1