

To: I 040271
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 7543

Operator: Wood Petroleum Corporation
Name & Address P.O. Box 947
Pratt, KS 67124

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor H-30, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 3:30 a.m. Day: 29 Month: 4 Year: 19 89

Plugging proposal received from Mike Thorp

(company name) H-30, Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1875' GL
Anhydrite 660-680'

RECEIVED
STATE CORPORATION COMMISSION

5-3-89
MAY 3 1989

Plugging Proposal Received by Steve Dornert
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 a.m. Day: 29 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 280' with 50 sx cement,
2nd plug at 150' with 50 sx cement,
3rd plug cement in 15' of 5 1/2" casing with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

A 12 1/4" bit, bit sub, and 2 drill collars were left in the hole. Bit is at 525'. Drill collars were backed off of. Top of drill collars are @ 465'. Had to wash hole back down from 90-240', plugged bit. Trip pipe, cleaned hole back out to 280' to plug.

Remarks: Used 60/40 Pozmix 2% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-8-89
INV. NO. 26647

Signed Stephen J. Pfeifer
(TECHNICIAN)

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 26, 1989
month day year

G.S./2.N/2.NE/4sec .35 Twp 26 S, Rg 12 East
West

OPERATOR: License # 7543
Name: Wood Petroleum Corp.
Address: P. O. Box 947
City/State/Zip: Pratt, KS 67124
Contact Person: Mark P. Stevenson
Phone: 316-672-7514

4290 feet from South line of Section
3960 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 5107
Name: 11-30, Inc.

County: Pratt
Lease Name: Mardis "J" Well # 1-35
Field Name: Stead South
Is this a Prorated Field? yes X no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 990
Ground Surface Elevation: 1875 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 240
Depth to bottom of usable water: 240
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 260
Length of Conductor pipe required: None
Projected Total Depth: 4500'
Formation at total depth: Simpson
Water Source for Drilling Operations:
X well farm pond other

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... X Infield ... X Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

If OAWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location: _____

DWR Permit #: N/A
Will Cores Be Taken? yes X no
If yes, proposed zone: _____

get 350' of 8 3/8 on 4-27-89

260' Alt. I Req.

AFFIDAVIT

FUSHER <u>Mike Tharp</u>	FORMATION	ELEVATION	STARTING TIME & DATE	COMPLETION TIME & DATE	1st PLUG @	FT. W/	SX
ID	@				2nd PLUG @	FT. W/	SX
SURFACE PIPE	@				3rd PLUG @	FT. W/	SX
ANHYDRITE					4th PLUG @	FT. W/	SX
					RAT HOLE CIRCULATED W/		SX
					MOUSE HOLE CIRCULATED W/		SX
					WATER WELL PLUGGED W/		SX
					CEMENT COMPANY		
					TECHNICIAN		

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1989

5-3-89
CONSERVATION DIVISION
Wichita, Kansas

5280	1980
4950	1650
4620	1320
4290	990
3960	660
3630	330
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

Spud date: _____ Agent: _____

REMEMBER TO:

- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field prorated orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.