

1 010178

90R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4864

Operator: Averada Corporation  
Name & Address: 105 N. Market, Suite 700  
Wichita, KS 67202

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company, Inc. License Number 5929  
Address Box 823, Great Bend, KS 67530

Company to plug at: Hour: 8:30 p.m. Day: 16 Month: 10 Year: 19 86

Plugging proposal received from Larry Curtis

(company name) Duke Drilling Company, Inc. (phone) 316-793-8366

were: To fill hole with heavy mud and spot cement through drill pipe

1st plug at Top of Arbuckle with 50 sx cement

2nd plug at Base of Anhydrite with 50 sx cement

3rd plug at 30' below surface casing with 40 sx cement

4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 p.m. Day: 16 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1170' with 50 sx cement

2nd plug at 380' with 40 sx cement

3rd plug at 40' with 10 sx cement

4th plug to circulate rathole with 15 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied  
(If additional description is necessary, use BACK of this form.)

INVOICED

STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

DATE 10-22-86

INV. NO. 15211

-10-21-86  
OCT 21 1986

API NUMBER 15-151-21,804-0000  
SW NW NE, SEC. 35, T 26 S, R 12 W/EX  
4290 feet from S section line  
2310 feet from E section line  
Lease Name Mardis Well # 2-35  
County Pratt 140.11  
Well Total Depth 4311 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 350

Signed Paul L. Lacey (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

(see rules on reverse side)

Starting Date Sept. 10, 1986  
 month day year 8/9

API Number 15- 151-21,804-0000

OPERATOR: License # 04864  
 Name Averada Corporation  
 Address 105 N. Market Suite 700  
 City/State/Zip Wichita, Kansas  
 Contact Person Kent A. Deutsch  
 Phone (316) 265-1401

SW-NW-NE Sec. 35 Twp. 26 S, Rg. 12 East  
4290 West  
2310 Ft. from South Line of Section  
2310 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet  
 County Pratt

CONTRACTOR: License # 5929  
 Name Duke Drilling  
 City/State Wichita, Kansas

Lease Name Mardis Well # 2-35

Well Drilled For: Well Class: Type Equipment:  
 Oil  SWD  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expt  Wildcat  Cable

Ground surface elevation 330 feet MSL  
 Domestic well within 330 feet:  yes  no  
 Municipal well within one mile:  yes  no

Depth to bottom of fresh water 150 Ft.  
 Depth to bottom of usable water 109 Ft. 250

Surface pipe by Alternate: 1 X 2  
 Surface pipe planned to be set 350 Ft.

Conductor pipe required none  
 Projected Total Depth 4500 Ft. feet

Formation Arbuckle

If OWWO: old well info as follows:  
 Operator .....  
 Well Name .....  
 Comp Date ..... Old Total Depth.....

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.  
 Date 8-8-86 Signature of Operator or Agent Kent A. Deutsch Title District Manager

For KCC Use:  
 Conductor Pipe Required ..... feet; Minimum Surface Pipe Required ..... 250 feet per Alt. 98  
 This Authorization Expires 3-9-87 Approved By 9-9-86

Spud 1:30  
350' 8 5/8  
ETD 4500  
Water Well old well  
Allied

98  
RCH/KCC

SW-NW-NE Sec. 35 Twp. 26 S, Rg. 12 East  
4290 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @	Top of Arbuckle	feet depth with	50	sxs of	60/40 Pozmix, 6% gel
2nd plug @	Base of Anhydrite	feet depth with	50	sxs of	" " "
3rd plug @	30' below surface casing	feet depth with	40	sxs of	" " "
4th plug @	40	feet depth with	10	sxs of	" " "
5th plug @		feet depth with		sxs of	
(2) Rathole with	15	sxs		(b) Mousehole with	sxs

PUSHER	FORMATION	FT. W/	SX
TD	@	FT. W/	SX
SURFACE PIPE	ELEVATION	FT. W/	SX
ANHYDRITE	STARTING TIME & DATE	FT. W/	SX
COMPLETION TIME & DATE	1st PLUG @	FT. W/	SX
2nd PLUG @	FT. W/	SX	
3rd PLUG @	FT. W/	SX	
4th PLUG @	FT. W/	SX	
RAT HOLE CIRCULATED W/	FT. W/	SX	
MOUSE HOLE CIRCULATED W/	FT. W/	SX	
WATER WELL PLUGGED W/	FT. W/	SX	
CEMENT COMPANY			
TECHNICIAN			

10-16-86  
plug 10:00 pm  
Depth 4311  
Allied America

checked 70  
2381  
 OCT 21 1986  
10-21-86