

15-151-1073-0000

1 080502

Docket No. D-01,281

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Completed 5-25-42

TECHNICIAN'S PLUGGING REPORT

Operator License # 5593

SW NW SE SW, SEC. 31, T 26 S, R 12 W/X

767 feet from S section line

1038 feet from E section line

Operator: B M & N Oil Co.  
Name & Address: 517 South Main  
Stafford, KS 67578

Lease Name Honeman Well # 1-W SWD

County Pratt 148.53

Well Total Depth 4570 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 892

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Bayse Well Service License Number 5670

Address P. O. Box 149, Stafford, KS 67578

Company to plug at: Hour: 2:00 pm Day: 18 Month: March Year: 19 86

Plugging proposal received from Marvin Bayse

(company name) Bayse Well Service (phone) 316-234-5235

were: 5 1/2" at 4324' 7" at 4388' Open Hole 5 1/2" has packer in hole at 4324' 829'  
cement lined tubing has parted.

Orders were issued according to hole conditions.

Spotted 100# hulls at 800', spotted 75 sx cement at 800'. Pulled tubing to  
400'. Spotted 25 sx cement. Let set 24 hours. Pumped 200 sx cement down 10 3/4".

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:00 pm Day: 20 Month: March Year: 19 86

ACTUAL PLUGGING REPORT Maximum pressure 100 psi and shut in 0.

Tagged cement at 824'. Spotted 200# hulls at 800' Pulled 2 joints of tubing and  
spotted 3 sx gel and 30 sx cement, 1 sack calcium chlorides.

1-19-86 Tagged cement at 824'. Put 1/2 yard of chat down 5 1/2". Tagged chat at 813'.

Spotted 200# of hulls at 790' plus 30 sx cement. Tagged cement at 787'. Pulled tubing

out of hole. Ran tubing back in hole and washed down to 210'. Circulated cement to top.

Pumped 50 sx down backside. Used 1000# hulls and 250 sx cement on backside. 205 sx cement

Remarks: down 5 1/2". Could not pump into 7". Used 60/40 Pozmix 6% gel.

No Recovery. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-1-86

STATE COM.

Witnessed

J. H. Metz  
(TECHNICIAN)

MAR 31 1986  
3-31-86  
CONSERVATION DIVISION

INV. NO. 13194  
3-20