

1 040213

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5217

Operator: S & K Oil Company

Name &

Address Box 559

Tulsa, OK 74101

API NUMBER 15-Drill Completion Date 6/18/83

C S/2 NW, SEC. 33, T 26 S, R 12 W/E

3300 feet from S section line

3960 feet from E section line

Lease Name Miskimen Well # 1

County Pratt 140.08

Well Total Depth 4310 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 355

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 5 Month: 1 Year: 19 89

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4303' PBTB 4255' Perfs at 4170-80, 3748-52, 3724-30, 3707-10, 3694-98'

1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls, and

175 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:30 a.m. Day: 5 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 5 sx cement on top of sand bridge with bailer,

2nd plug pumped down 10 3/4" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls, released 10 3/4" wiper plug and pumped 175 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2691' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-12-89

INV. NO. 23647

Signed Stephen J. Pfeiffer
(TECHNICIAN)

WELLEX

BOND LOG

**ACOUSTIC CEMENT
BOND LOG**

COMP. S. AND K. OIL COMPANY WELL MISKIMEN NO. 3 FIELD N. E. PRATT COUNTY PRATT ST. KANSAS	COMPANY 8 AND K OIL COMPANY		
	WELL MISKIMEN NO. 3		
	FIELD N. E. PRATT		
	COUNTY PRATT STATE KANSAS		
API NO. NA		OTHER SERVICES	
LOCATION C - 8/2 - MM		PERFORATE	
SEC. 33 TWP. 26S RGE. 12W			
PERMANENT DATUM GROUND LEVEL		ELEV. 1897	
LOG MEASURED FROM KELLY BUSHING		11 FT. ABOVE PERM. DATUM	
DRILLING MEASURED FROM KELLY BUSHING		ELEV. K.B. 1908 D.F. 1905 C.L. 1897	
DATE & TIME LOGGED	04/28/88 11:00 AM	TYPE OF FLUID IN HOLE	WATER
RUN NO.	ONE	DENSITY OF FLUID	--
DEPTH - DRILLER	4325	FLUID LEVEL	2900
DEPTH - WELEX	4320	CEMENT TOP EST. - LOGGED	3370
BTM. LOGGED INTERVAL	4310	EQUIPMENT & LOCATION	51088 BT BEND
TOP LOGGED INTERVAL	3200	RECORDED BY	MR. J. GILZINGER
MAX TEMP. DEGREE	121	WITNESSED BY	MR. D. WILSON
CEMENTING DATA	SURFACE STRING	PROTECTION STRING	PRODUCTION STRING
DATE/TIME CEMENTED			
PRIMARY/SQUEEZE	PRIMARY		
EXPECTED COMP. STRENGTH			
CEMENT VOLUME			
CEMENT TYPE/WEIGHT			
FORMULATION	150 SKS 40/60		
	POZ		
MUD TYPE/MUD WEIGHT			
RUN NO.	BOREHOLE RECORD		CASING AND TUBING RECORD
	BIT	FROM TO	SIZE WGT. FROM TO
ONE	15 1/2"	0 355	10 3/4" 0 355
TWO	7 7/8"	355 4305	5 1/2" 0 4303

TD 4310
5 1/2" - TD 4303
Plug - 1st Cem. 4255
Viola - Perf 4170-4180
KC Laos. Perf 3748-3752
3724-3730