

040217

1-17

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,559-0000

TECHNICIAN'S PLUGGING REPORT

RECEIVED  
JAN 20 1989  
1-20-89

SW SW SW, SEC. 33, T 26 S, R 12 WEX

370 feet from S section line

4915 feet from E section line

Operator License # 3243

Lease Name Williams Well # 1

Operator: Commonwealth Petroleum Corporation

County Pratt 153.47

Name & Address P.O. Box 2458

Well Total Depth 4722 feet

Hutchinson, KS 67504

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address P.O. Box 108, Geneseo, KS 67444

Company to plug at: Hour: 11:15 a.m. Day: 17 Month: 1 Year: 1989

Plugging proposal received from Tom Keaston

(company name) Nicholas Casing Pulling (phone) 316-824-6338

were: 5 1/2" at 4721' PBD 4116' Perfs at 3860-70, 4332-50'

1st plug sand back to 3810' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 17 Month: 1 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 3810' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 550 psi and shut in 325 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2105' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-23-89

INV. NO. 13771

Signed Stephen J. Pfeifer  
(TECHNICIAN)