

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25266-00-00
Spot: NWSWSWSE Sec/Twnshp/Rge: 27-16S-22W
495 feet from S Section Line, 2475 feet from E Section Line
Lease Name: HAIR/WAGNER UNIT Well #: 1-27
County: NESS Total Vertical Depth: 4600 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		WITH 2 SX CMT
DVT		1731		CMT TO SURFACE
PROD	4.5	4598	0	WITH 475 SX CMT
SURF	8.625	310		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2014 3:00 PM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL COMPANY LLC Phone: (620) 793-0915

Proposed Plugging Method: SET CIBP @ 4250' WITH 2 SX CMT. RTIH TO 1750' & CIRCULATE CMT TO 0'. CHECK BACKSIDE

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 08/27/2014 4:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4250' WITH 2 SX CMT. RAN TBG TO 1750' & CIRCULATED CMT TO SURFACE WITH 180 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT, PRESSURING TO 600#. TOPPED OFF 4 1/2" CASING WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4399	4402		
4393	4396		
4386	4390		
4377	4383		
4299	4304		

Received
KANSAS CORPORATION COMMISSION


Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

SEP 12 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed 
9.12.14 CKM (TECHNICIAN)

RECEIVED
AUG 29 2014
KCC DODGE CITY