

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20156-00-00
Spot: NENENWSW Sec/Twnshp/Rge: 35-23S-31W
2587 feet from S Section Line, 4010 feet from E Section Line
Lease Name: SNELL WALTER Well #: 1
County: FINNEY Total Vertical Depth: 2710 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: 3033 NW 63RD ST - STE 151
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1248		
PROD	4.5	2707	0	WITH 150 SX CMT
SURF	8.625	331		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/27/2014 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 08/27/2014 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CUT TBG OFF AT 2048'. SPOT 25 SX CMT AT 2017'. SET CIBP @ 1248'. TEST CASING. HOLDING. PERFORATE 4 HOLES AT 1200'. INJECTION RATE 2 BPM @ 300#. SPOT 80 SX CMT HALF IN & HALF OUT OF PERFS WITH HULLS IN LAST HALF. PERFORATE 4 HOLES AT 350'. CIRCULATE CMT TO SURFACE WITH 130 SX CMT, LEAVING THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2670	2676		

Received
KANSAS CORPORATION COMMISSION

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL.

SEP 12 2014

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

AUG 29 2014

KCC DODGE CITY

Signed

Ken Jehlik
9.12.14 ccm

(TECHNICIAN)

SP

Form CP-2/3